

INSTITUTO DE CIENCIAS DE LA CONSTRUCCIÓN EDUARDO TORROJA

C/ Serrano Galvache, 4. 28033 Madrid (Spain) Tel.: (+34) 91 302 0440 www.ietcc.csic.es gestiondit@ietcc.csic.es dit.ietcc.csic.es





European Technical Assessment ETA 23/ 0812 of 10/ 10/ 2023

English translation prepared by IETcc. Original version in Spanish language

General Part

Technical Assessment Body issuing the European Technical Assessment: Instituto de Ciencias de la Construcción Eduardo Torroja (IETcc)

Trade name of the construction product	APLICOAT HF
Product family to which the construction product belongs	Liquid Applied Bridge deck Waterproofing
Manufacturer	Aplinor Xpraytech Systems, S.L. Polígono industrial de Olloniego, Parcela B 36-37, nave 1. 33660 Oviedo, Asturias, Spain
Manufacturing plant(s)	Plant 1.
This European Technical Assessment contains	7 pages, including 1 Annex, which contains confidential information and is not included in the European Technical Assessment when that assessment is publicly disseminated
This European Technical Assessment is issued in accordance with Regulation (EU) No 305/2011, on the basis of	EAD 030675-00-0107 Liquid applied Bridge Deck waterproofing Kits

Translations of this European Technical Assessment in other languages shall fully correspond to the original issued document and should be identified as such.

Communication of this European Technical Assessment, including transmission by electronic means, shall be in full (excepted the confidential Annex(es) referred to above). However, partial reproduction may be made, with the written consent of the issuing Technical Assessment Body. Any partial reproduction has to be identified as such.



Specific parts

1 Technical description of the product

APLICOAT HF is a liquid applied bridge deck waterproofing kit based on polyurea resin. The waterproof membrane consists of a polyurea resins, bi-component, elastomeric; which once polymerised conforms a jointless elastic lining, in form of a layer completely bonded to the support (concrete).

This liquid applied bridge deck waterproofing kit is not intended to receive direct vehicular traffic in service and in this case will always be used beneath overlays of asphalt (mastic asphalt, asphalt concrete or concrete) which may have a protective character and/or additional waterproofing function. The kit "APLICOAT HF" is designed and installed in accordance with the manufacturer, design and installation instructions.

This kit comprises the following components, which are factory produced by the manufacturer.

Components	Trade name	Consumption	Thickness	
Primer	APLICOAT PRIMER 100 (epoxy) +	0,4- 0,5 kg/m ²	0.35 - 0.45 mm	
	Broadcast of quartz sand (0,3- 0,8 mm. thick)	+ 0,7 kg/m ²	0,00 0,10 1111	
Adhesion promoter for overlapping	Light abrasion of the surface + cleaning with DISOLVENTE APLINOR + APLICOAT PRIMER PU	0,1 kg/m²	Non film-forming (0 mm)	
Waterproofing membrane	APLICOAT HF	≥ 2 kg/m²	1,90 mm	
Top coat	APLICOAT PRIMER PUR F + Broadcast of quartz sand (0,30,8 mm. thick) until saturation and removal of the excess of sand, when resin gets dry.	0,5 kg/m ² + 2-3 kg/m ²	0,90 mm	

2 Specification of the intended use in accordance with the applicable European Assessment Document (hereinafter EAD)

2.1 Intended use(s)

The intended use of Liquid Applied Bridge Deck Waterproofing Kits is the waterproofing of the concrete deck of the bridge preventing or controlling the passage of water to the support.

This kit is made of non-load bearing construction elements. It does not contribute directly to the stability of the bridge on which is installed, but it can contribute its durability by providing enhanced protection from the effect of weathering.

This applied kit fulfils the Basic works requirements nº 1 (Mechanical resistance and stability), nº 3 (Hygiene, health and the environment) and nº 4 (Safety in use) of the European Regulation 305/11.

The kit is suitable for the following use categories according: (A) with overlay and intended to receive vehicular traffic:

- A.1 Overlay asphalt concrete applied at (160 \pm 10) °C (CBM).
- A,2 Overlay of mastic asphalt applied at 220 °C to 250 °C (MA).
- A.3 Non-asphaltic overlays.

In the manufacturer's technical dossier (MTD) to this ETA the manufacturer gives specific information concerning the application of the product.

Kits used beneath ballast are not covered under the scope of this ETA.

2.2 Relevant general conditions for the use of the kit

The provisions made in this European Technical Assessment are based on an assumed working life of 25 years from installation in the works, according to EAD 030675-00-0107, provided that the conditions lay down for the installation, packaging, transport and storage as well as appropriate use, maintenance and repair are met. In this respect.

ETA 23/0812- version 1 of 10/10/2023 - page 2 of 7



The indications given on the working life cannot be interpreted as a guarantee given neither by the product manufacturer nor by EOTA nor by the Technical Assessment Body issuing this ETA, but are regarded only as a means for choosing the right product in relation to the expected economically reasonable working life of the works.

Installation. The kit is installed on site. It is the responsibility of the manufacturer to guarantee that the information about design and installation of these kits is effectively communicated to the concerned people. This information can be given using reproductions of the respective parts of this European Technical Assessment. Besides, all the data concerning the execution shall be clearly indicated on the packaging and/or the enclosed instruction sheets using one or several illustrations.

<u>Design</u>. In the MTD the manufacture gives information on the quantities consumed and the processing, which shall lead to a thickness of the deck waterproofing \geq 2,7 mm.

<u>Usage range of temperatures.</u> The range of operational temperatures of the waterproofing layer is -40 °C to +60 °C. EN 1991-1-5 provides a correlation between the shade air temperature and bridge temperature component.

<u>Condition of support</u>. The support on which the waterproofing is applied shall have a surface texture of 0.3 mm to 1.5 mm. EN 1766: 2000, clause 7.2 or EN 13036-1: 2002 describe suitable methods for measuring surface texture.

The age of the concrete support is normally assumed to be in excess of three weeks and unless specific assessments have been made the cohesive strength of the concrete surface shall be greater than 1.5 MPa.

<u>Weather conditions</u>. The waterproofing system cannot be put in place during rain, hail or snow. The support temperature shall be greater than 5 °C and at least 3 °C above the dew point, unless specific assessments have been made.

Execution. Particularly, it is recommended to consider:

- The kit installation has to be carried out by qualified installers,
- it can only be used the components of the kit indicated in this ETA,
- the supervision of the amount of material used (kg/m²) and the control visual to check that each coat covers totally the one below, can ensure the minimum thickness of the kits,
- inspection of deck surface (cleanliness and correct preparation) before applying the deck waterproofing,
- It is applied by a hot spray applied machines. Temperatures, component A, 70 °C. Component B, 65 °C.
 Pressure about 170 bars.

Before, the installation of APLICOAT HF, it is recommended to read its security card.

Use, maintenance and repair of the works. In deteriorated areas of the waterproof layers, they will be repaired removing all the deteriorated layers. Afterwards, the new product will be assembled following the installation instruction and the new coats must overlap, at least 3 cm, to the coat no deteriorated.

3 Performance of the product and references to the methods used for its assessment

The identification tests and the assessment for the intended use of "APLICOAT HF" according to the Basic Work Requirements (BWR) were carried out in compliance with EAD 030675-00-0107. The characteristics of each system shall correspond to the respective values laid down in following tables of this ETA, checked by IETcc.

Methods of verification and of assessing and judging are listed afterwards.

ETA 23/0812- version 1 of 10/10/2023 - page 3 of 7



3.1 Mechanical resistance and stability (BWR 1)

Basic requirement for construction works 1; Mechanical resistance and stability					
Esser	tial characteristic	Relevant E/	clause in AD	Condition test	Values
Bond strength (kit to support)		2.2.1		P1, S0, T5	2.5 MPa A/B
Capacity to bridge cracks (-20 °C)		2.2	2.2	P1, S1+S2, T2	Watertight
Resistance to chloride ion penetration		2.2	2.3	P1, S0, T5	0.039 %
Resistance to	Resistance to perforation	-	2.2.4.1	P1, S0, T5	Pass (I4)
dynamic actions	Resistance to compaction of asphalt concrete	2.2.4	2.2.4.2	P1, S1.2, T5	Resistant and watertight
	Bond strength (kit to support)	2.2.5		P1, S1, T5	2.2 MPa A/B
Resistance to heat impact (indirect method) (170 °C)	Tensile stress (initial- ageing) 10 mm/min 23 °C / 1 mm/m -10 °C Elongation (initial- ageing) 10 mm/min 23 °C / 1 mm/m -10 °C			P1, S0/S1, T5 / T3	19 /24 MPa 22 / 24 MPa 210 / 331 % 228 / 301 %
	Capacity to bridge cracks	2.2.5	2.2.2	P1, S1+S2, T2	Watertight
Resistance to shear	Asphalt concrete 160 °C (CBM)			P1, S1.2., T5	0,2 MPa
between the substrate and overlay	Mastic Asphalt 250 °C (MA)	2.:	2.6	P1, S1.1, T5	0,34 MPa
Water-tightness (23 °C)	1	2.2	2.7	P1, S0, T5	Watertight
	Low temperature		2.2.2	P1, S1+S2, T2	Watertight
Resistance to high and low service	Bond strength to the support at +40 °C, -10 °C or -20 °C	2.2.8	2.2.1		NPA
temperatures	Resistance to shear to support (2.2.6) at +40 °C and/or –10 °C		2.2.6		NPA
Capacity to penetrate p	ores in the support	2.2	2.9		NPA
Resistance to flow (ass horizontal surfaces)	sociated with the application to non-	2.2.10		P1, S0, T5	0 %
Dry film thickness		2.2.11		P1, S0, T5	2.7 mm
Resistance to the effects of climatic	Bond strength to the support 5 °C	2212 27	221	P1 S0 T5	2.0 MPa A/B
conditions on application	Bond strength to the support 40 °C	2.2.12	2.2.1	11,00,10	2.3 MPa A/B
	Moisture Content (MC)	-			NPA
Resistance to the effects of quality of	Day Joints (OA) (24h/ 48h)	2.2.13		P4, S0, T5	2.3 / 2.4 MPa A/B
the support (SC)	Section Joints (up to six months) (OA) (7d)			P4, S0, T5	1.7 MPa A/B
Resistance to contact	Variation in mass (edges sealed/ edges not sealed)	2.2.14		P1 S5 1 T5	0.17 / 0.18 %
with water (Wa)	Micro hardness Initial/ageing (variation)				86º / 84º (-2 %)
Resistance to alkali	Variation in mass (edges sealed/ edges not sealed)	2.2.15		P1, S5.2, T5	0.3 %
solution contact (AI)	Micro hardness Initial/ageing (variation)				86º / 78º (-9 %)
Resistance to oil, petrol or, diesel contact		2.2	.16		NPA
Resistance to bitumen contact (Bi)	Micro hardness Initial/ageing	2.2	2.17	P1, S5.3, T5	84º/81º (- 3 %)
Resistance to heat ageing (HA)	Capacity to bridge cracks		2.2.2	P1, S1+S2, T2	Watertight
	tensile stress (initial- ageing) 10 mm/min 23 °C / 1 mm/m -10 °C Elongation (initial- ageing)	2.2.18	2.2.18	P1, S0/S2, T5 / T3	19 /24 MPa 22 / 24 MPa 210 / 331 %
	10 mm/min 23 ºC / 1 mm/m -10 ºC		2.2.18		228 / 301 %
	Bond strength to the support		2.2.1	P1, S2, T5	2.4 MPa A/B

ETA 23/0812- version 1 of 10/10/2023 - page 4 of 7



3.2 Hygiene, health and environment (BWR 3)

Basic requirement for construction works 3: Hygiene, health, and the environment					
Essential characteristic	Relevant clause in EAD	Performance			
Content, emission and/or release of dangerous substances	2.2.20	NPA			

3.3 Safety and accessibility in use (BWR 4)

Basic requirement for construction works 4: Safety and accessibility in use				
Esse	ntial characteristic	Relevant clause in EAD	Condition test	Performance
Bond strength	Mastic Asphalt (250 °C)	2.2.21	P1, S1.1, T5	1.3 MPa B/C
(kit to overlay)	Asphalt concrete (160 °C)		P3, S1.2, T5	0.64 MPa A/B
	Slipperiness	2.2.22		NPA
Resistance to Abrasion / Wear		2.2.23		NPA

3.4 Durability due to climatic (BWR 1 and 4 (high and low temperatures)

Durability due to climatic: Resistance to freeze/thaw (FT)				
Essential characteristic	Relevant clause in EAD		Condition test	Performance
Bond strength to support	2.2.24	2.2.1	P1, S3, T5	1.3 MPa A/B
Resistance to shear to support / overlay MA		2.2.6	P1, S3., T5	0.21

4 Assessment and verification of constancy of performance (hereinafter AVCP) system applied, with reference to its legal base

4.1 System of assessment and verification of constancy of performance

According to the decision 2003/722//EC of the European Commission⁽¹⁾ the system of assessment and verification of constancy of performance (see Annex V to Regulation (EU) n^o 305/2011) given in the following table applies.

Product	Intended uses	Level or Classes	System
APLICOAT HF	Liquid Applied Bridge deck Waterproofing	Any	2+

This system of attestation of conformity +2 is defined as follows:

<u>Tasks for the manufacturer</u>. Initial type-testing of the product, Factory production control and Testing of samples taken at the factory in accordance with a prescribed test plan.

Tasks for the notified body: Certification of factory production control on the basis of:

- o Initial inspection of factory and of factory production control.
- o Continuous surveillance (annual), assessment and assessment of factory production control.

ETA 23/0812- version 1 of 10/10/2023 - page 5 of 7



⁽¹⁾ Official Journal of the European Communities L229/14 of 20.08.1997

5 Technical details necessary for the implementation of the AVCP system, as provided for in the applicable EAD

Technical details necessary for the implementation of the AVCP system are laid down in the control plan which is deposited at IETcc².

5.1 Tasks of the manufacturer

Factory production control. The manufacturer shall exercise permanent internal control of production. All the elements, requirements and provisions adopted by the manufacturer shall be documented in a systematic manner in the form of written policies and procedures, including records of results performed. This production control system shall ensure that the product is in conformity with this ETA.

The manufacturer may only use components stated in the technical documentation of this ETA including Control Plan. The incoming raw materials are subjected to verifications by the manufacturer before acceptance.

The factory production control shall be in accordance with the Control Plan. The results of factory production control shall be recorded and evaluated in accordance with the provisions of the Control Plan

Initial type-testing of the product. The initial type-testing have been conducted by the IETcc to issue this ETA in accordance with the EAD 030675-00-0107 Liquid applied Bridge Deck waterproofing Kits. The verifications underlying this ETA have been furnished on samples from the current production.

Other tasks of the manufacturer. The manufacturer shall, on the basis of a contract, involve a body which is notified for the tasks referred to in section 4 in order to undertake the actions laid down in this clause. For this purpose, the control plan shall be handed over by the manufacturer to the notified bodies involved.

The manufacturer shall make a declaration of conformity, stating that the construction product is in conformity with the provisions of this ETA.

5.2 Tasks of notified bodies

Initial inspection of factory and of factory production control. The Notified Body shall ascertain that, in accordance with the Control Plan, the factory (in particular the employees and the equipment) and the factory production control are suitable to ensure continuous and orderly manufacturing of the components according to the specifications mentioned in clause 2 of this ETA.

Continuous surveillance, assessment and assessment of factory production control, in accordance with the provisions laid down in the control plan, at least one per year.

The notified body shall retain the essential points of its actions referred to above and state the results obtained and conclusions drawn in a written report. The notified certification body involved by the manufacturer shall issue an EC Certificate of factory production control stating the conformity of the provisions of this ETA.

In cases where the provisions of the ETA and its control plan are no longer fulfilled the notified certification body shall withdraw the certificate of conformity and inform to IETcc without delay.

² The Control Plan is a confidential part of the ETA and only handed over to the notified certification body involved in the assessment and verification of constancy of performance.

ETA 23/0812- version 1 of 10/10/2023 - page 6 of 7



Issued in Madrid on 10 october 2023

By

Director on behalf of Instituto de Ciencias de la Construcción Eduardo Torroja (IETcc – CSIC)

ETA 23/0812- version 1 of 10/10/2023 - page 7 of 7

